

AQ1570

The AQ1570 uses Prolitec's patented technology to diffuse fragrance and odor treatment products into the air. This modular system was designed for direct diffusion in up to four spaces with a single powered central control unit.



Diffuse directly with up to 4 cartridge heads per system.

Perfectly scents spaces up to 150,000 cubic feet per cartridge head.

50 intensity levels and timing options give you control.

Tiny droplets convert to vapor within milliseconds.



AQ1570

| | | |
|---------------------------|-----------------|--|
| Technical Specifications | Type | Up to 4 nebulizer heads |
| | Cartridge | 2500mL recyclable |
| | Droplet size | About one micron |
| Power Specifications | Input | 100 – 240 VAC, 1.5A Max, 50/60 Hz |
| | Protection | Switching power supply |
| | Internal | Real time clock with permanent backup battery |
| | Output | 15VDC at 4A |
| Performance & Settings | Coverage | Up to 150,000 ft ³ (4,250 m ³) per cartridge head |
| | Programs | Up to 21 start/stop times per day 24/7 mode |
| | Settings | 50 intensity levels |
| | Off-cycle | 30 seconds, 2 minutes or 7 minutes |
| | Enclosure | Stainless steel with swinging door, IP22 |
| | Safety Approval | FCC part 15, CE, RoHS Compliant, UL Power Supply |
| | Environment | 0° to 40° C, <85% Humidity |
| Dimensions & Installation | Size | CCU: 36cm x 35cm x 17.2cm Cartridge head: 35.6cm x 18cm x 17.2cm |
| | Weight | CCU: 5.1kg with 4 modules Cartridge head: 2.5 kg empty |
| | Mounting | Wall mount |